



Perit Ruben Sciortino
 B.E.&A (Hons), A.&C.E. Warrant No.: 476
Perit Alexander Bianchi
 B.E.&A (Hons), A.&C.E. Warrant No.: 560
Perit Malcolm Tong
 Dip.DFS, B.Sc.(Hons), M.Eng (Struct.) (Meit.)
 Warrant No.: 1059

Architects, Civil Engineers & Structural Consultants

47, Sorenson, Danny Cremona Street, T: 21247356, M:79311234, F: 27247356
 Hamrun HMR 1511 E: ruben@rsdesign.eu

Date: 19th January 2021

Job. No: 814/10

Client: Din L-Art Helwa

Contractor:

Project: Rehabilitation of Torri Mamo

Location: Marsascala

Item	Description	Qty	Unit	Rate	Amount
Restoration Works					
Note:					
A	<i>Costs to include for all testing as per specifications</i>				
B	<i>All rates for restoration works to include all necessary scaffolding, carting away surplus material, use of crane, statutory permits, electricity, water and transport expenses.</i>				
C	<i>In all the restoration works, the thickness of stonework used shall match that of the walls on site.</i>				
D	<i>Works have to be carried out in stages as instructed by the Architect or his appointed representative</i>				
1	Carefully take down existing deteriorated stonework as instructed and replace to average an depth of 125mm of damaged stonework with irregular sized softstone blocks (ta' l-ordni) of matching size	38.35	m ²		
2	Clean and rake out all open joints and flush point all joints in a hydraulic lime and sand mixture.	38.35	m ²		
Total				€	
VAT at 18%				€	
Grand Total				€	